



- 1 Proposed Play Equipment**
Upgraded play space to include a maritime themed play experience suitable for all ages. The play equipment is designed to challenge minds and bodies, allow children to create their own adventures, set boundaries and encourage role play and social interaction. Refer SK02 for further detail.
- 2 Hill Slides**
Replace existing hill slides with toddler and primary aged tunnel slides. Staggered sandstone blocks at varying heights allow children to naturally climb the embankment to reach the top of the slides.
- 3 Turf Areas**
Existing swings and park table to be removed and turfed over. Play experiences to be consolidated into location 1.
- 4 Multi-Purpose Court**
Apply new line marking to existing basketball court. Provide new multi-use goal suitable for basketball, netball and soccer sports.
- 5 Picnic Facilities (Large)**
Remove existing shelter and provide new large shelter with lighting and wind breaks near existing carpark. Provide new single BBQ, drinking fountain and bin.
- 6 Carpark Path**
Construct path from carpark to picnic facilities to increase accessibility. Extend garden area and install sandstone blocks and boulders for informal seating.

- 7 Table Setting**
Remove existing table settings and provide new table setting connected by a path between multi-purpose court and playground.
- 8 Picnic Facilities (Small)**
Remove existing shelters and BBQ and provide new shelter with lighting, wind breaks and double BBQ connected by a path to the carpark. To include new double bins and connect to existing bike racks.
- 9 John Street Carpark**
Extend car spaces along John Street and provide 2x all abilities spaces to cater for improved all abilities.
- 10 Foreshore Path**
Provide new 3m wide path along Queens Esplanade foreshore.
- 11 Platform Seats**
Provide platform seats for group seating connected to new path.
- 12 Seats**
Provide new seats under natural shade of trees connected to new path. Reinstate tribute plaques where required.
- 13 Shelters**
Provide new shelters and table settings.
- 14 Park Sign**
Provide new park sign.
- 15 Telescope**
Provide interpretive sign and 2x telescopes connected to the new path for shorebird watching along the foreshore. Foreshore experiences to allow better access and interface with RCC's naturally wonderful coastline.
- 16 Sculpture Artwork**
Space allocated for future sculptural artwork (TBC).
- 17 Foreshore Vegetation**
Reinstate vegetation to further protect the foreshore from future erosion.

- 18 Beach Experience**
Increase foreshore experience to allow better access and interface with RCC's naturally wonderful coastline. Accessible beach matting can be temporarily installed to increase access to the foreshore (TBC).
- 19 Mooroondu Road Path**
Provide path connection along Mooroondu Road and connect to existing.
- 20 Bollards and Seating**
Renew existing bollards around park perimeter. Extend existing mulch areas and provide sandstone block seating and boulders.
- 21 Garden and Planting**
Provide new garden between public amenities and playground. Install relocated sandstone block boulders and additional 2x tree plantings.
- 22 Playground Path**
Improve all abilities access throughout park by providing a 2m wide path around playground which connects to the new foreshore path, shelters, public amenities, multi-purpose court and hill slides.
- 23 Contemplative Circle**
Remove contemplative circle and reinstate area with turf and soil to allow for kick-a-bout space.
- 24 Path Graphics**
Apply stencilling/wording on new playground and foreshore path to reinforce interactions with the foreshore and maritime theme (TBC).
- 25 Lighting**
Low level solar bollard lighting to be installed around the shelter and path closest to the playground, public amenities and John Street carpark. Install up lighting to both existing fig trees in play space.
- 26 Embankment Stabilisation**
Provide improvements to embankment to protect from further erosion.

- Legend**
- SWD — Existing Stormwater Services
 - Proposed Stormwater Upgrade
 - Proposed Scour Protection Mat
 - Proposed Stormwater Outlet
 - Proposed Stormwater Culvert/Pipe
 - Proposed Grouted Rock Shoulder
 - Partially buried Geotextile Sandbag Seawall
 - Moreton Bay Marine Park Boundary
 - 27 Sand Re-nourishment
 - Saltmarsh/Native Planting and Sandstone Seating Block
 - Shallow Open Channel

Section A-A Proposed Geotextile Sandbag Seawall

